




FENCE SPECIFICATION NOTES

- **FENCE POSTS** - 4" SQUARE X 11 GA. (STANDARD, OTHER POSTS APPLICATION SPECIFIC).  
MINIMUM 50 KSI YIELD AND 55KSI TENSILE  
MINIMUM G90 GALVANIZED PER ASTM A787 AND A1057
- **FENCE PICKETS** - 5" WIDE, LIQUID COLOR COATED (IN STANDARD COLORS) AND ROLL FORMED  
.017" THICK FULL-HARD 80 KSI STEEL  
MINIMUM G90 GALVANIZED PER ASTM A653  
2-COAT THERMO-CURED PAINT SYSTEM CONSISTING OF:  
PRIMER UNDERCOAT  
FLUOROPOLYMER TOP COAT CONTAINING MINIMUM 70 PERCENT POLYVINYLIDENE DIFLUORIDE BY WEIGHT.  
COMPLIES WITH THE PHYSICAL PROPERTIES AND COATING PERFORMANCE REQUIREMENTS OF AAMA 621
- **C-CHANNEL RAILS**-  
ROLL FORMED 14 GAUGE GRADE 50 MINIMUM STEEL PER ASTM A653  
MINIMUM G90 GALVANIZED
- **U-CHANNELS AND RAIL BRACKETS**-  
FORMED 14 GAUGE GRADE 50 MINIMUM STEEL PER ASTM A653  
MINIMUM G90 GALVANIZED
- **HARDWARE** -  
PICKET FASTENERS PER ANSI B1.13M  
SERIES 302 STAINLESS STEEL 6-LOBE PIN-IN SECURITY TRUSS HEAD  
PULL-OUT STRENGTH 5500 NEWTONS  
CARRIAGE BOLTS AND NUTS FOR RAIL ATTACHMENT  
1/4-20" ASTM F593 18-8 STAINLESS STEEL  
THREAD-FORMING SCREWS FOR RAIL BRACKET AND CHANNEL ATTACHMENT  
1/4-14" 410 STAINLESS STEEL SELF-DRILLING SCREW



PICKET LAYOUT



NOTES:

- INSTALLATION TO BE COMPLETED IN ACCORDANCE WITH MANUFACTURER'S SPECIFICATIONS.
- DO NOT SCALE DRAWING.
- THIS DRAWING IS INTENDED FOR USE BY ARCHITECTS, ENGINEERS, CONTRACTORS, CONSULTANTS AND DESIGN PROFESSIONALS FOR PLANNING PURPOSES ONLY. THIS DRAWING MAY NOT BE USED FOR CONSTRUCTION.
- ALL INFORMATION CONTAINED HERE WAS CURRENT AT THE TIME OF DEVELOPMENT BUT MUST BE REVIEWED AND APPROVED BY THE PRODUCT MANUFACTURER TO BE CONSIDERED ACCURATE.

<b>SUBMITTALS ARE NOT FOR CONSTRUCTION PROVIDE FIELD MEASUREMENT PRIOR TO FABRICATION</b>		<b>BASTEEL</b> PERIMETER SYSTEMS™											
Kynar 500® Top Coat Colors													
<small>Custom colors available. Please request color samples.</small>													
<table border="1"> <tr> <td>NAME</td> <td>DATE</td> <td>CUSTOMER:</td> </tr> <tr> <td>REP</td> <td>3/22/2021</td> <td>GENERIC SUBMITTAL</td> </tr> </table>		NAME	DATE	CUSTOMER:	REP	3/22/2021	GENERIC SUBMITTAL	<table border="1"> <tr> <td>FINISH</td> <td>TITLE:</td> </tr> <tr> <td>POWDER COAT</td> <td>WINDSOR FENCE GENERIC SUBMITTAL</td> </tr> </table>		FINISH	TITLE:	POWDER COAT	WINDSOR FENCE GENERIC SUBMITTAL
NAME	DATE	CUSTOMER:											
REP	3/22/2021	GENERIC SUBMITTAL											
FINISH	TITLE:												
POWDER COAT	WINDSOR FENCE GENERIC SUBMITTAL												
<small>PROPRIETARY AND CONFIDENTIAL THE INFORMATION CONTAINED IN THIS DRAWING IS THE SOLE PROPERTY OF BASTEEL PERIMETER SYSTEMS. ANY REPRODUCTION IN PART OR AS A WHOLE WITHOUT THE WRITTEN PERMISSION OF BASTEEL PERIMETER SYSTEMS IS PROHIBITED.</small>		<table border="1"> <tr> <td>SIZE</td> <td>DWG.</td> <td>REV</td> </tr> <tr> <td>C</td> <td>C-SUBMITTAL</td> <td>1</td> </tr> </table>		SIZE	DWG.	REV	C	C-SUBMITTAL	1				
SIZE	DWG.	REV											
C	C-SUBMITTAL	1											
		WEIGHT:											